

Quote

Date: August 4, 2022
To: Tracy Burnett
Chatham County Recreation Director

Project: Northeast Park Multipurpose Field
Chapel Hill, NC
Ref: 204060

Sourcewell

Master Project: 199030, Contract Number: 071619-MSL, Expiration: 08/27/2023
Category: Sports lighting with related supplies and services

All purchase orders should note the following:
Sourcewell purchase – contract number: 071619-MSL

Quotation Price – Materials Delivered to Job Site and Installation

Soccer Field – 360' x 195' \$ 213,292
(Includes Use Tax)

Pricing furnished is effective for 60 days unless otherwise noted and is considered confidential.

Light-Structure System with Total Light Control – TLC for LED™ technology

Guaranteed Lighting Performance

- Guaranteed light levels of 30FC

System Description

- 4 Pre-cast concrete bases with integrated lightning grounding
- 4 Galvanized steel poles
- Factory wired and tested remote electrical component enclosures
- Pole length, factory assembled wire harnesses
- 20 Factory wired poletop luminaire assemblies
- 20 Factory aimed and assembled luminaires
- UL Listed assemblies

Control Systems and Services

- Control-Link® Control and Monitoring system to provide remote on/off and dimming (high/medium/low) control and performance monitoring with 24/7 customer support

Operation and Warranty Services

- Reduction of energy and maintenance costs by 40% to 85% over typical 1500W metal halide equipment
- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 Team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors



Quote

Delivery Timing

8 - 12 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations.

Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.

Quote is based on:

- Shipment of entire project together to one location.
- 480 Volt, 3 Phase electrical system.
- Structural code and wind speed = IBC 2018, 115 MPH Wind Speed, Risk Category II, Exposure C.
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees.
- Includes supply and installation of Musco system including underground wiring and conduit, service entrance panel board, and controls by a licensed contractor.
- Standard soil conditions – rock, bottomless, wet or unsuitable soil may require additional engineering, special installation methods and additional cost.
- Confirmation of pole locations prior to production.

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.

Brad Marolf
North Carolina Field Sales Representative
Musco Sports Lighting, LLC
Phone: 336.813.0194
E-mail: brad.marolf@musco.com

