



REMIT PAYMENTS TO:

Wire/ACH:
LilyPad EV
Bank: United Missouri Bank
Routing# 101000695
Checking# 9871859819

Paper Checks:
LilyPad EV
c/o United Missouri Bank
7109 W 80th St
Overland Park, KS 66204

LilyPad EV
9801 W. 100th Terr
Overland Park, KS 66212
(913) 269-2453
keith.anderson@lilypadev.com
www.lilypadev.com

Quote

ADDRESS

Chatham County, NC
Kevin Lindley
28 County Services Rd.
Pittsboro, NC 27312

SHIP TO

Chatham County, NC c/o
Smithfields Chicken N BBQ
Kevin Lindley
14215 US 64
Pittsboro, NC 27312 US

QUOTE # 3022

DATE 08/10/2021

Table with 4 columns: DESCRIPTION, QTY, EACH, AMOUNT. Contains 5 rows of product details including ChargePoint:CPE250C-625-CCS1-200A-CHD, ChargePoint:CPCLD-ENTERPRISE-DC-5, ChargePoint:CPE250-CMT-IMPERIAL, ChargePoint:CPE250-ASSURE-5, and ChargePoint:OM-INSTALL-SITEVALID.

Thank you for your business.

DESCRIPTION	QTY	EACH	AMOUNT
-------------	-----	------	--------

transformers, panels, breakers, wiring, cellular coverage and that the station installation meets all ChargePoint published requirements and local codes. A site is defined as a group of stations all connected to the same gateway station. A successful Site Validation is a prerequisite to purchase ChargePoint Assure. OM-INSTALL-SITEVALID is priced per gateway station.

ChargePoint:CPSUPPORT-ACTIVE	1	0.00	0.00
-------------------------------------	---	------	------

Initial Station Activation & Configuration Service includes activation of cloud services and configuration of radio groups, custom groups, connections, access control, visibility control, pricing, reports and alerts. One time initial service per station.

Installation:INSTALL	1	22,550.00	22,550.00
-----------------------------	---	-----------	-----------

Scope of Work:

- Install CPE 250 fast DC charger in designated location
- 400 Amp 600 Volt main lug with (1) 100 amp 3 phase service rated breaker 25k A.I.C rated
- Freestanding metal structure for service equipment
- 2 inch parallel conduits and 3/0 feeders to pad mounted transformer
- Cut curb out and remove for charger installation
- Install small retaining wall with 6x6 treated lumber or concrete curb (if necessary)
- Pour new concrete pad at curb level for CPE250
- Feeder and conduit from service panel to charger location
- Stub (2) additional conduits for future stations
- Stub DC Conduit and communication conduits for future CPE 250 install
- 2 bollards to protect station
- Striping as indicated in drawing below
- Post(s) and install for required signage
- Permit and inspections as required by local AHJ

Exceptions

- This proposal is based on a standard install and subject to change based on specific site variables or AJH requirements and fees

Terms and Conditions

Plans/Specifications-Electrical work requested by others not indicated on plans and/or specifications shall not be part of this agreement
 Underground Work-All trenching assumes reasonable digging conditions with no major rock that would require extra equipment and material to excavate. In such cases, there may be additional charges based on evaluation of the conditions.

Weather-Project schedule may be delayed to severe weather.

Contractor is not responsible for delays in schedule due to severe weather.

Change Orders-Deviation or alteration to the scope of this agreement, including plans or specification, shall be executed on receipt of written orders

Code and Installation Practices-Material and equipment supplied by Electrical Contractor shall be installed in accordance with the National Electrical Code and local electrical building code, and standard electrical practices. Requirements that are not codified as of the date of this proposal are excluded from this quotation.

Warranty-Warranty of electrical material and equipment supplied by Electrical Contractor shall be for a period of one year from the date of final invoice. No warranty will be provided for material and equipment

DESCRIPTION	QTY	EACH	AMOUNT
-------------	-----	------	--------

supplied by others, and no warranty shall be performed while invoice(s), including change order(s) are past due. Waste-Electrical Contractor will dispose of waste generated from construction.

Sales Tax	1	5,225.15	5,225.15
Sales Tax calculated by AvaTax on Wed 11 Aug 16:30:03 UTC 2021			

STANDARD TERMS & CONDITIONS:	SUBTOTAL	84,019.15
• Quote good for 30 days	TAX (0%)	0.00
• Payment Terms: Net 30	SHIPPING	650.00
• Manufacturer standard warranty applies	TOTAL	\$84,669.15
• Standard Lead-time: 30-60 days		
• Shipping: FOB Origin, Freight Prepaid & Charged Back		
• Customer responsible to verify AT&T/Verizon 4G cell coverage of -85dbm or better at installation location. -70dbm is better than -85dbm.		
• Returns of unopened packages subject to restocking charges. Opened packages may not be returned.		
• If installation included inquote, we reserve the right to invoice you for the charging station products at delivery and for installation when complete.		
• Any Installation costs do not include unforeseen rock or other obstacles found while trenching or boring		

PAYMENT INSTRUCTIONS
for entry into your accounting system

Send Wire or ACH payments to:
LilyPad EV
Bank: United Missouri Bank
Routing# 101000695
Checking# 9871859819

-or-
Send Payment Check to
LilyPad EV
c/o UMB Bank
7109 W 80th St
Overland Park, KS 66204

Accepted By

Accepted Date